

## **WIFA Project Construction Sign Guidelines and Specifications**

If required by Exhibit B Section 4.6 of the WIFA Loan Agreement, Project Publicity/Signage, the Local Borrower will establish at commencement of construction one or more WIFA construction signs at prominent locations at or near the construction site per the following guidance and attached specifications.

1. The Local Borrower or general contractor shall furnish and install a construction sign(s) for identification of the WIFA project. The sign shall be constructed in accordance with the enclosed drawing/specifications. (If the contractor chooses to erect a separate sign, it may be attached to or adjacent to the project sign, but no other contractor or subcontractor or material signs will be permitted on the WIFA sign.)
2. The cost of preparation and erection of the sign is loan eligible. All costs associated with signage must be reasonable.
3. The construction sign for identification of the WIFA project will be installed prior to commencement of construction at a location which is near the project site and amenable to public viewing.
4. The sign will be adequately supported with regard to site conditions and will be an adequate distance above the prevailing grade to permit public viewing.
5. The sign will be constructed of a 4.0 feet by 8.0 feet exterior type high density overlaid plywood or other sign material of equivalent quality and framed with nominal 2 inch by 4 inch wood of suitable grade.
6. The sign will be painted with black lettering on a matte white background. The WIFA logo will be painted with process blue color and black lettering in strict proportion to the attached detail.
7. Lettering will be of professional quality and in accordance with the attached drawing; all lettering will be in proportion to the sizes shown and centered on the sign.
8. Information specified on the attached detail will be displayed on the sign.
9. Any additional information displayed on the sign will not detract from or displace the information required in the drawing. Changes must be approved by WIFA.
10. The sign will be maintained in good condition until completion of the construction project.
11. The sign will be removed and appropriately disposed of when the construction is complete and accepted by WIFA.

**WIFA Project Construction Sign Guidelines and Specifications**  
**Town of Clarkdale Twin 5s Water Main Replacement**



**Sponsor:** Town of Clarkdale  
**Mayor:** Doug Van Gausig  
**Vice Mayor:** Richard Dehnert  
**Council:** Curtiss Bohall, Bill Regner,  
Reynold P. Radoccia  
**Engineer:** Shephard-Wesnitzer, Inc.  
**Contractor:** Felix Construction Co.



Sample

**Financed by the Water Infrastructure Finance Authority of Arizona  
(Arizona's State Revolving Fund) and the EPA.**

**State of Arizona  
Governor Douglas A. Ducey**

**U.S. EPA  
Andrew Wheeler, Administrator**